NORTH WIND 2 kW HIGH RELIABILITY WIND SYSTEM

Phase II Fabrication and Test

June 1982

Donald J. Mayer John H. Norton, Jr.

Prepared by the

North Wind Power Company, Inc. P.O. Box 315 Warren, Vermont 05674

For

Rockwell International Corporation Energy Systems Group Rocky Flats Plant Wind Systems Program Post Office Box 464 Golden, Colorado 80401

Subcontract No. PF-71768F

As a part of

United States Department of Energy Wind Energy Technology Division Federal Wind Energy Program

DOE Contract No. DE-ACO4-76DP03533

#### ABSTRACT

This report describes the Phase II activities (fabrication and testing) performed by the North Wind Power Company, Inc. relative to development of a 2 kW high reliability wind energy conversion system intended for use in remote locations and harsh environments. This program was conducted under Contract No. PF71768F awarded by Rockwell International Energy Systems Group in January 1978 as a part of the United States Department of Energy Federal Wind Energy Program. Phase I activities pertained to system design and analysis and results have been previously published (Reference 1).

Warren Bollmeier was the Rockwell Technical monitor and L. D. Cullen and William Joslyn were Rockwell contract administrators. Clay Waldon was Rockwell's Test Engineer for this project. The final version of the report was extensively edited at Rocky Flats.

North Wind personnel instrumental during Phase II of this project were Donald J. Mayer, John H. Norton, Jr., John Kueffner, Clint Coleman, and Allan Russell.

# TABLE OF CONTENTS

		Page
1.0	Introduction	1
2.0	Design Overview	4
3.0	Design Changes Resulting from Analysis	9
	3.1 HR2 Alternator Design Changes	9 9
4.0	Fabrication and Assembly of HR2 Prototypes	11
5.0	Design Changes and Contractor Testing of Prototype #1	18
6.0	Design Changes of Prototype #2	22
7.0	Design Changes and Contractor Testing of Prototype #3	22
8.0	Summary of Phase II Design Changes and Prototype Modifications	23
9.0	Updated Costs/Economic Projection	25
10.0	Updated Reliability Analysis	27
11.0	Maintenance Procedures	29
12.0	Conclusions	29
13.0	References	30
Appen	dix A - Drawing Revisions	31

# FIGURES

		Page
1.	North Wind 2 kW High Reliability Prototype	2
2.	North Wind HR System Schematic	5
3.	Variable Axis Rotor Control System (VARCS) Operational Modes	6
4.	Balancing of HR2 Blades	12
5.	Completed VARCS Assembly	15
6.	Completed HR2 Alternator	16
7.	Example of Acceptance Criteria	17
8.	Contractor Power Curve	19
9.	Contractor Hysteresis Curve	19
10.	HR2 Reliability Flow Chart	28
	TABLES	
I	North Wind Power Company Phase II Organizational Chart	3
II	Phase II Schedule	3
III	North Wind 2 kW High Reliability System Specifications	7
I۷	Phase II Alternator Modifications	9
٧	Contractor Dynamometer Test Results	14
VI	Blade Deflection Tests	20
VII	Blade Material and Fabrication Specifications	21
VIII	Significant Phase II Design Changes	24

#### NOMENCLATURE

alternating current ac annual operating and maintenance (cost) MOA American Society for Testing of Materials **ASTM** centrigrade C cubic centimeter CC Critical Design Review **CDR** centimeter CM  $C_{\mathsf{S}}$ Coefficient of System Performance equals that portion of total kinetic energy in the wind available to the rotor capture area which is converted to useable electrical output by the system. Coefficient of Performance equals that portion of the  $q^{0}$ total kinetic energy in the wind available to the rotor capture area which is converted to torque at the main shaft by the rotor. decibels (A-weighted scale) dBA direct current dc degrees F Fahrenheit FCR Fixed Charged Rate Final Design Review FDR ft feet gram gm HZ hertz High Reliability 2 kW - North Wind trade name for the com-HR2TM mercial version of the SWECS developed under this contract. IC Installed Cost

inch

in

K - Spring constant expressed as a slope in inch pounds of force per degree of torsional deflection.

kg - kilogram

kVA - kilovolt amperes

kW - kilowatt

kWh - kilowatt hours

 failure rate expressed as number of failures per million hours.

1b - pound

Lundel Rotor - Also known as interdigitated rotor where field coil is wound around central core post with individual field poles wrapped around the outside.

m - meter

m<sup>2</sup> - square meter

mm - millimeter

mph - miles per hour

MTBF - Mean Time Between Failure expressed in years.

N-m - newton meter

NWPCo - North Wind Power Company

% – percent

± - plus or minus

PDR - Preliminary Design Review

Ø - phase

r/R - variation (r) from blade chord line at nondimensional radial station (R) of blade.

REA - Rural Electrification Administration

RFP - Request for Proposals (when used in text)

rpm - revolutions per minute

SWECS - Small Wind Energy Conversion System

- one year t

- volt

- Variable Axis Rotor Control System - North Wind Trade name for the HR2 control system. VARCSTM

٧ - annual average (mean) wind speed

		Ψ.
		ē
		1.00
		,
		u

#### 1.0 INTRODUCTION

In January 1978, the North Wind Power Company, Inc. was awarded a contract to design, fabricate and test a 2 kW wind system capable of unattended operation at remote sites and under severe environmental conditions. The contract was sponsored by the U.S. Department of Energy and administered by Rockwell International Corporation as part of an effort to expedite the use of small (under 100 kW) wind systems. Contract activities were divided into two phases: 1) system design and analysis; and 2) prototype fabrication and testing.

After contract initiation North Wind proceeded with the design of a high reliability wind system that would produce 2.2 kW of power at wind speeds of 9 m/s (20 mph). During Phase I of the program, a predecessor of the proposed design was procured and tested in a wind tunnel and in the free stream to observe operational characteristics (see Reference 1). An analytical procedure was developed for designing and modeling the proposed variable axis rotor control system (VARCS<sup>TM</sup>). This procedure was then verified by extensive testing of preprototype components. A low-speed, three-phase alternator with a Lundel type rotor was also approved for Phase II prototype fabrication and testing.

This report presents the results of Phase II of the program in which three (3) production prototypes were fabricated and tested. It also contains descriptions of some design and analysis activities which continued into Phase II. Prototype #1 was tested at North Wind Power Company's facilities for one and one-half months prior to shipment to Rocky Flats. Testing at Rocky Flats continued until a bent shaft was discovered, at which time unit #1 was replaced with prototype #2. Testing of #2 (Figure 1) is ongoing at Rocky Flats and results will be published at a later date. Since the start of unit #2 testing, a third prototype has been installed at North Wind for parallel testing. Upon completion of the in-house test program, this unit will be shipped to Rocky Flats. A contractor organizational chart and Phase II schedule are shown in Tables I and II, respectively. Phase II activities were completed during December 1980.




Figure 1
North Wind 2 kW High Reliability Prototype

TABLE I

North Wind Power Company
Phase II Organizational Chart





TABLE II
Phase II Schedule



# 2.0 DESIGN OVERVIEW - NORTH WIND HIGH RELIABILITY 2 kW SWECS (HR2)

The design philosophy of North Wind Power Company was to base the development of this small wind system on older concepts which the company has been able to refine and augment by using analytical modeling techniques and advanced materials. Design concepts such as a three-bladed upwind rotor, a direct-drive electrical generator, and the Parris-Dunn method of speed control by rotor tilt-back were applied to the HR2. North Wind Power Company's objective for this program was to develop a design emphasizing simplicity, durability, and cost-effectiveness without degrading performance or reliability. The direct-drive generator and variable axis rotor control system (VARCS) were selected to meet this design objective. Figure 2 is a schematic of the overall configuration of the HR2.

The VARCS was selected to be the cornerstone of the HR2's system reliability. The rotor tilt-back design reduces the complexity and expense associated with a variable pitch hub assembly requiring an additional folding tail or shutdown/reorientation device for protection in extreme winds. Figure 3 is a schematic of VARCS operation. A direct-drive, low-speed generator was developed to meet the program's cost and performance goals by eliminating the need for a high-speed generator employing a gear box. Use of these components minimizes the number of moving parts in the HR2, thereby contributing to increase reliability and minimize maintenance.

The HR2 is designed to produce 2200 watts of electric power at wind speeds of 9 m/s (20 mph) and maintain a 700 watt continuous load at a site with average winds of 5.4 m/s (12 mph). Table III lists the prototype's final system specifications.

# Contract Design Specifications (Untested):

- Mean time between failures: calculated at 131,000 hours.
- · Maintenance: less than one man day per year.
- Design life: 25 years.
- Operating costs: less than 1% of the installed cost.
- Operating temperature range: -70°C to 60°C (-94°F to 140°F).
- High wind survival speed: 74 m/s (165 mph).
- Environmentally sealed and corrosion protected.





Figure 2 North Wind HR System Schematic


# Figure 3

# Variable Axis Rotor Control System (VARCS) Operational Modes




1. STANDARD OPERATIONAL MODE

50 TILT AT START-UP TO ACCOUNT FOR BLADE DEFLECTION
CUT-IN WIND SPEED: 10MPH
MAX WIND SPEED THIS MODE: 21MPH
MAX POWER OUTPUT THIS MODE: 2203WATTS
MAX RPM THIS MODE: 250RPM



2. AXIS ROTATION VERTICALLY

OVERSPEED CONTROL CONTROL INITIATION: 21MPH SHUTDOWN: 105MPH




3. SHUT DOWN --- 105mph

AXIS ROTATION TO 90

POWER AND RPM'S APPROACH 0

SPRING TENSION REALIGNS ROTOR AS GUSTS SUBSIDE



4. MANUAL SHUT DOWN
SERVICE AND MAINTENANCE

# TABLE III

# NORTH WIND 2 kW HIGH RELIABILITY SYSTEM SPECIFICATIONS

General Description	3-bladed, horizontal axis, upwind
Physical Description Weight (Tess tower) Rotor Diameter Tower Height	356 kg (785 lb) 5 m (16.4 ft) 12.2 m (40 ft)
Operational Characteristics  Cut-in Wind Speed Speed Control Initiation System Shutdown Survival Wind Speed Rated Output @ Wind Speed Rotational Speed @ Rated Output Cs @ Rated Output Yearly Output in V = 5.36 m/s (12 mph) = 6.70 m/s (15 mph) = 7.15 m/s (16 mph) = 8.04 m/s (18 mph)	7,800 kWhrs 8,400 kWhrs
Rotor Weight (Blades, Hub) Diameter Capture Area Solidity Tip Speed Ratio Cp at Rated Output	41 kg (90 lb) 5 m (16.4 ft) 19.63 m <sup>2</sup> (2.11.2 ft <sup>2</sup> ) .04 7.5 .41
Blades Material Planform Twist Airfoil	Sitka spruce (aircraft grade) Linear taper from 200 mm (8") @ r/R = .3 to 80 mm (3.1") @ tip Non-linear from 12.5° @ r/R = .3 to .5° @ tip G625 from r/R = .1 to r/R .3, N60 from r/R = .3 to tip (modified)
Hub Material Type	Cast and wrought steel (ASTM 148-73 Class 80-50) Fixed Pitch

# TABLE III (Continued)

Generator Type	3 Ø synchronous alternator
Nominal Voltage	(Lundel rotor) 24 vdc
Size	458 mm (18") by 368 mm (14.5")
Number of Poles	12
Synchronous Speed @ 25 Hz	250 rpm
Rated Power @ Speed	2.2 kW @ 250 rpm
Efficiency Weight	70% @ rated speed and output 133 kg (295 lb)
Speed Control	
Type	Variable Axis Rotor Control
Spring	System (VARCS) Spiral Torsion Spring
Spi ing	K = 71 in. lbs/degree
Rotor Tilt Range	10° to 90° (from horizontal to vertical)
Yaw Control	Free yawing
Tower	
Type	Unarco Rohn 45 GSR double guyed
Material	Galvanized steel
Height	12.2 m (40 ft)
Weight	700 kg (1555 lb)
System Cost (1000th unit)	
Unit	\$2867
Tower	700
Storage Installation	2000 (24 volt/800 amp hour) 1200 (site dependent)
TOTAL	\$6767
Cost of Energy	
Installed Cost	\$6767
Fixed Charge Rate Annual Operations & Maintenance Cost	.085 \$135
Annual Kilowatt Hours Produced	10,981 (assume 6.7 m/s [15 mph]
Author Kilowada Haara II adaaca	average)
COE = IC (FCR) + AOM  KWhrs	
$COE = \frac{6767 (.085) + 135}{7800}$	
COE = \$.091 per kilowatt hour	

#### 3.0 DESIGN CHANGES RESULTING FROM ANALYSIS

#### 3.1 HR2 Alternator Design Changes

Analysis and in-house component testing resulted in several design changes to the HR2 alternator during Phase II.

In-house component testing indicated that additional magnetic material was needed in the Lundel rotor to improve the residual magnetism and, hence, self-excitation characteristics. Magnetic material was subsequently added in the form of a 6" diameter 1/4" thick hardened steel disc. Later, a hardened tool steel washer was added in the alternator rotor between the two halves of the Lundel to further improve self-excitation. The alternator modifications detailed (in sequence) in Table IV reduced self-excitation rpm from 250 to below 200.

PHASE II ALTERNATOR MODIFICATIONS

TABLE IV

	DESIGNATION	DIA. @ AIRGAP	STATOR WINDING	ROTOR WINDING
3B	0.625 01 tool steel magnetic washer	15.375	9 T, 4 in hand #13	858 T #17
3C 3D	Two .0625 01 washers .125 A2 tool steel	15.375	9 T, 4 in hand #13	858 T #17
4	magnetic washer .125 A2 tool steel	15.375	9 T, 4 in hand #13	858 T #17
4	magnetic washer	15.375	11 T, 4 in hand #14	540 T #14

# 3.2 Other Design Changes Resulting from Analysis

A power conduit connector was replaced with a flexible cast silicon boot between the VARCS shaft and saddle to improve and simplify tower installation and reduce unit cost.

The spring hub and shaft design was simplified to improve manufacturability. This change reduced the sub-assembly parts count from six (6) to two (2) and lowered manufacturing costs by eliminating a redundant bearing assembly.

The VARCS spring length was shortened to increase the spring rate to 71 in lb/degrees. The modification was based on test data which dictated a revision of the computer model. Redesign with the revised model indicated a stiffer spring was required to match the desired power curve and raise the peak output from 1500 watts to 2200 watts at a wind speed of 9 m/s (20 mph).

Tail arms were lengthened by 1" to generate greater yaw movement, thus providing greater yaw stability with respect to the precessional forces generated during tilt-back and tilt-down.

#### 4.0 FABRICATION AND ASSEMBLY OF HR2 PROTOTYPES

In the construction of the HR2 prototypes, all major components, with the exception of the rotor blades, were manufactured and machined out-of-house. These included rotor hub and shaft; alternator and castings; saddle mount; VARCS springs; plates and discs; endbells; tower top; and tail-vane. At the North Wind facilities, only assembly work, miscellaneous parts fabrication, and component testing were carried out.

#### Rotor

The rotor blade fabrication process was accomplished by employing the blade fabrication techniques which North Wind had previously developed for the North Wind Eagle (Reference 2). Each three-blade set for the prototype models began with rough-cut Sitka spruce blades fabricated from 2"x8"x98" stock by a vendor using hand carving techniques. The rough blades were inspected to assure proper chord angle within 1/2° of the specifications. Using an in-house-developed angle cutting machine, which utilizes a belt sander and a molded blade-support platform, each blade was ground to the correct chord angle and given an acceptable surface finish.

The roots of the blades were then drilled for all rotor hub attachment points. The leading and trailing edges of each blade were inspected with templates to determine the extent to which the blade required final finish sanding in order to achieve the correct airfoil sections with consistent precision. The first coat of one part polyurethane with paint was applied and then the self-adhering leading edge protective tape fitted to the blade. Each blade was finished with two more coats of paint. As the final step in producing a complete HR2 blade set, the blades were balanced by means of a gravity moment measuring device, using the heaviest blade as the reference (see Figure 4). Where necessary, lead weights were attached with brass screws at the root of the blades to achieve a matched and balanced blade set. The specific balancing modifications to each set were recorded and catalogued.

Figure 4 Balancing of HR2 Blades

The two-part rotor hub (casting and pressure plate) was then fitted with all three blades to assure proper overall rotor balance. The entire fabrication and assembly check-out required two skilled workers 48 manhours per rotor.

#### VARCS

The VARCS spring was manufactured by an outside vendor from a 144" long 1/2" by 1 1/2" bar of 4140 steel. The bar was heated and coiled into a spiral approximately 13" in diameter with a 3/8" space between each coil. The completed coil was then annealed and shipped to North Wind.

In the completed VARCS assembly (Figure 5), the spring was clamped into the VARCS hub at the inside coil and mounted on the VARCS shaft. At the outer radius, the spring was attached by a bracket to the VARCS disc mounted on the alternator assembly. A bar bolted to the VARCS disc and bearing on the inactive excess portion of the spring acted as a bridle to maintain the concentricity of the spring as the machine pitched back. This bar also acted as a 90° positive stop.

#### Alternator

Alternator assembly consisted of setting the pre-stacked and wound stator in the rear endbell and dressing out the power leads for connection to the rectifiers, then assembling the rotor. Rotor assembly involved pressing the front Lundel casting on the shaft, fitting the completed field coil around the Lundel core and bolting the rear Lundel casting to the front casting.

The rotor coil leads were dressed out along the shaft and the front and rear bearings pressed on. The entire assembly was completed when the finished rotor was lowered into the rear endbell and stator, the front endbell bolted on and all connections to the rectifiers and slip rings completed (see Figure 6). This finished assembly was then tested on the dynamometer for final acceptance. Results are presented in Table V.

TABLE V
Contractor Dynamometer Test Results.

Load Setting	Field Current (I <sub>2</sub> )	Field Voltage (E <sub>2</sub> )	Input Torque (N-M)	RPM	Input Power = .105 O*RPM	Output Current (I <sub>1</sub> )	Output Voltage (E <sub>1</sub> )	Output Watts (W <sub>2</sub> )	Eff (P <sub>2</sub> )
- 0 25 50 75 80 85 90 95 100 110 120 130 140 150 160 170 180 190 200 210 220 150 125 100 60	14.3 13.7 12.5 11 10 9.6 9.5 9.3 8.8 8.6 8.3 8.7.7 7.6.9 6.6 6.2 5.9 4.9 4.3	52 50 48 42 40 39 38.5 38 37 35.4 34.6 33.5 32.4 31 28.5 28.7 25 23.9 19.6 17.8 32 32 33 33 33 33 33 33 33 33	80 136 159 160 143 138 140 146 147 150 150 150 144 139 136 131 124 91 82	250 2011 aps 275 250 225 200	2100 3570 4174 4200 3754 3623 3625 3833 3859 3938 3938 3938 3938 3780 3649 3570 3439	5 24 50 62 64 67 69 72 78 80 83 86 89 93 94 94 94 94 93 83 78	52 50 48 42 40 39 38.5 38 37 35.4 34.6 33.5 32.4 31 28.5 28.7 25 23.9 19.6 17.8 32 32 32 32 32	1152 2100 2480 2496 2580 2622 2664 2761 2768 2781 2786 2759 2651 2632 2510 2350 2223 1627 1388 3328 2720 2208 1280	55 59 59 59 69 72 72 71 70 70 70 78 70 68
25 10	7.8 6.7	32 27.5	44 24	175 150	808 378	16 5	32 27.5	512 138	63 36



Figure 5
Completed VARCS Assembly

Figure 6 Completed HR2 Alternator

#### Quality Assurance

Quality control during Phase II prototype fabrication and assembly procedures was maintained by the Production Manager at North Wind Power Company. Key dimensions of all components and specific tolerances were monitored and maintained. Acceptance criteria were developed for all critical subassemblies and test procedures carried out to verify compliance. A sample of acceptance criteria is shown in Figure 7.




Figure 7
Example of Acceptance Criteria

#### 5.0 DESIGN CHANGES AND CONTRACTOR TESTING OF PROTOTYPE #1

Prior to shipment to Rocky Flats, North Wind tested Prototype #1 on its truck test facility and on a tower at its Warren facility. Prototype #1 was instrumented for the following operational parameters: current, voltage, power output, rpm, wind speed, pitch, yaw and wind direction. Data were reduced from all these parameters both as instantaneous values and as averages by using the digitizing program on the "Arga Wind Tape" (Reference 1). Data obtained from current, rpm, and wind speed curves were calculated and averaged. For calculation of average power, the voltages were averaged over the period and multiplied by the average current (Figure 8).

Values obtained by these methods fell within a narrow band up to control velocity and tracked well the theoretical calculations (Figure 9). This wide divergence after tilt-back was confirmed in testing at Rocky Flats and was assumed to be due to control hystersis.

Contractor testing continued from mid-July to mid-August 1979. During this period the machine operated while connected to a battery bank. Wind speeds as high as 26 m/s (60 mph) were recorded during thunderstorms. During one such storm, a blade was broken when it deflected into the tower. This failure was attributed to a particularly soft (light-weight) blade and insufficient pre-pitch of the rotor to provide adequate tower clearance. Consequently, blade tests were performed resulting in an increase in pre-pitch from 5° to 10°. Blade specifications for weight were increased to assure sufficient material density and, hence, strength. Procedures and test results of the blade deflection tests are shown in Table VI. The modified material and fabrication specifications are shown in Table VII.




Figure 8
Contractor Power Curve





Figure 9
Contractor Hysteresis Curve

TABLE VI BLADE DEFLECTION TESTS

#### Procedure:

Each test blade was bolted to the rotor hub casting and pressure plate, which were, in turn, clamped and bolted to a workbench top, upwind side of the blade facing up. Test weights were applied at the .7R point (69"/1.75m) and blade deflections were measured at the tip, as diagrammed below:



#### Results:

Blade	Description	Weight	Weight, w(lbs)	Deflection (in)
5m, N6O#7	Finished Painted	9# 11-1/4oz.	94	12.75
5m, N6O#7 (broken)	Finished Painted w/inlaid lead	7# 6-1/2oz.	94	19.25
5m, N6O#8	"J", finished bare	6# 15-1/4qz.	94	16.
5m, N6O#8	"M", raw full root	9# 6-1/4oz.	94	12.5
5m, N60#8	"M", finished painted	8# 7-1/4oz.	94	13.875

#### TABLE VII

#### BLADE MATERIAL AND FABRICATION SPECIFICATIONS

#### Blade Material Specifications

Wood for blade to be "Sitka spruce," "select structural," maximum moisture content of 19% and specific gravity of 0.4,  $\pm 0.01$ .

Wood shall be selected with minimum defects, for 12" length at rotor shaft end. No defects, including knots, checks, etc., shall be permitted at connections or upwind of the quarter chord over blade length.

Wood shall be straight-grained, with fibers parallel to the length of the blade.

#### Blade Fabrication Specifications and Tolerances

Weight	9 pounds, plus or minus 8 ounces (see material specifications above)
Butt Width	5 15/16", plus or minus 1/16"
Butt Thickness	7/8", plus or minus 1/64"
Station Twist Angle	Template, plus or minus 1/2° (measured on upwind surface)
Station Chord Length	Template, plus or minus 1/16"
Bend-over Length	Plus or minus 1/4" (measured to reference, using upwind surface as base)

#### 6.0 DESIGN CHANGES TO PROTOTYPE #2

The most important design change made to prototype #2 was a result of test experience obtained at Rocky Flats with the discovery that the main shaft of prototype #1 was bent directly behind the hub casting. This bend occurred along the axis of one of the three blades. Although no wind load could be identified as the cause, calculations of the shaft section properties at that point revealed that sufficient force to bend the shaft could be applied by service personnel at the blade tip during installation or maintenance.

Following this development at Rocky Flats, North Wind Power Company redesigned the shaft taper at the hub to provide approximately 40% additional section. The shaft material was respecified from AISI 1141 to AISI 4340, hardened to RC 35. This new shaft was retrofitted to Prototypes #2 and #3.

Due to preliminary results from Rocky Flats, which indicated an instability in torsion at the upper limit of the operating range (400 rpm), the blades of prototypes #2 and #3 were also redesigned for additional structure. The new blade design provided 15% additional section at the quarter chord, resulting in a 25% increase in factor of safety. Both shaft and blade redesign were based on the performance and reliability criteria discussed in Section 8.0. The phenomenon was later determined to be due to the bent shaft discussed above, rather than instability. Prototype #2 is currently undergoing testing at Rocky Flats.

#### 7.0 DESIGN CHANGES AND CONTRACTOR TESTING OF PROTOTYPE #3

In November 1979, the third prototype was installed at North Wind Power Company. Initially, high noise levels were recorded as rpm approached 400 and assumed to be due to the soft blade deflecting torsionally at high rpm. Shortly after this observation, a redesigned set of blades was put into operation which met the specifications developed on the basis of the

Rocky Flats test experience, and no excessive noise levels were recorded. This system operated with no difficulty in a "no load" configuration until March 1980. However, in late March during a storm with gusts to 17.9 m/s (40 mph), all three blades were broken. Examinations revealed the cause of this failure to be blade impact with the tail vane. The ninety degree stop (actually found to be 93°) had maintained only 2" of clearance, which was insufficient for protection from high gust-induced pitch rates. This, and all stops, were then modified to 88° to provide 12" of clearance in the pitch-back mode of operation.

There have been little performance data collected in the company's free-stream testing of prototype #3. The main objective of the free-stream testing is to acquire operational hours on the prototype, while the acquisition of additional empirical data is left to Rocky Flats.

#### 8.0 SUMMARY OF PHASE II DESIGN CHANGES AND PROTOTYPE MODIFICATIONS

There were four criteria which governed all design change decisions made on the HR2 prior to and during prototype construction. Each design change or modification made to the prototypes was evaluated and implemented for its potential to improve 1) manufacturability (reduce costs, simplify construction); 2) reliability (increase part rating or reduce parts count); 3) maintainability (considering a remote site location); and 4) performance, (increase system efficiency and output or reduce wear and stress).

In addition to the blade, shaft and VARCS tilt-back modifications (described previously), there have been numerous small changes to HR2 drawings. These drawings are presently in the possession of Rocky Flats and changes are listed in Appendix A. None of the Phase I analyses of reliability cost and energy output were significantly altered by Phase II modifications.

Table VIII indicates the overall scope of Phase II design changes; however, many simple mechanical drawing updates or corrections are not listed.

TABLE VIII

# Significant Phase II Design Changes

SUBSYSTEM	PART NAME	PART NO.	DESCRIPTION OF CHANGE	REASON
Alternator	Field Rotor	2k120	Added .125" hardened steel washer between Lundel castings to provide higher residual field magnetism.	Performance - lowered self- excitation rpm from 250 to 175.
Rotor	Blades	2k210	Moved airfoil transition section outboard airfoil selection from 12% to 14% to stiffen blade.	Reliability - provided addi- tional out-of-plane strength and torsional stiffness.
Drive Train	Main Shaft		Redesigned shaft taper at hub to give 40% additional section. Re- specified shaft material to AISI 4340, hardened to RC 35.	Reliability - strengthened shaft to prevent bending from loading at blade tip.
VARCS	90° stop assembly	1	Add assembly to the VARCS mechanism consisting of arm attached to hub and stop bracket attached to disc to provide positive stop for 88° tilt-back.	Performance - prevented over-pitch and consequential intersection of tail with plane of turbine rotation.
	Power Conduit	1	Replace connector with flexible cast silicon boot between VARCS shaft and saddle.	Manufacturability and Maintenance - reduced unit cost by approximately \$200 and simplified installation procedure.
	Spring Hub & Shaft	1 1	Simplify Design	Manufacturability
	VARCS Spring	8 8	Shorten spring length to increase spring rate to 71 in lb/deg.	Performance – improved maximum output from 1.5 kW to 2 kW.
	Tail Arms	\$ \$	Lengthen tail arms to provide more yaw stability.	Performance - improved yaw stability during tilt-back and tilt-down.

# 9.0 UPDATED COSTS/ECONOMIC PROJECTION

## 1. Prototype Costs

Code	Sub Assembly	Cost of 1st Unit
100 200 300 400 500 600 800 900 1300 TOTAL	Alternator Rotor VARCS Saddle Tail Stub Tower Electrical Conditioning Electrical Regulation Manual Shutdown	\$2100 700 1170 894 53 525 84 300 74 \$5890
Additional Cost	:S	175 \$6065

## 2. Estimated System Costs

	Cost of 1st unit (1979 dollars)\$6065*	
	Cost of 100th unit (1979 dollars)\$4390*	
	Cost of 1000th unit (1979 dollars)\$2508*	
	Cost of 1000th unit (1977 dollars) including overhead and profit\$2867	
	Dollars per pound for 1000th unit (1977 dollars)\$4.59/pound	d
۲ (	ost does not include overhead and profit.	

# 3. Estimated Turnkey Costs

#### 1977 dollars

Wind machine (1000th machi	ne)\$2867
Tower (40 ft. Rohn 45 GSR)	\$ 700
Installation costs (assumes local labor & re includes concrete, site	elatively accessible site; preparation & labor)
Batteries	\$2000
TOTAL TURNKEY COST	\$6767**

<sup>\*\*</sup>Turnkey costs can be as much as 100% higher depending upon site accessibility, storage requirements and required auxiliary generated facilities.

### 4. Cost of Energy Calculation

Base Data:

IC = Initial installed cost (turnkey) = \$6767.00
FCR = Fixed Charge Rate (commercial) = 0.085
AOM = Annual Operation & Maintenance Cost = 135.00
AKWH = Annual Kilowatt Hours produced (assumes 15 mph mean wind) = 7800 kilowatt hours

For purposes of comparison with other DOE-funded prototypes, the cost of energy (COE) is calculated using the following formula specified by Rockwell:

COE = 
$$\frac{\text{(IC)} \quad (\text{FCR}) + (\text{AOM})}{\text{(AKWH)}}$$
  
COE =  $\frac{6767 \quad (0.085) + 135}{7800}$   
COE = \$.091 = 9¢ kilowatt hour

#### 10.0 UPDATED RELIABILITY ANALYSIS

All modifications that were made to the HR2 during Phase II are within the scope of reliability data developed in Phase I. The calculated mean time between failures (MTBF) for this machine is fifteen (15) years. Figure 10 is a reliability chart of the major systems showing subassembly reliability, major system reliability, and total reliability.

Assumptions used in generating Figure 10 are outlined below:

- a. Reliability figures assume that the maintenance schedule is adhered to.
- b. Slip rings, brushes and blades are replaced and/or refinished as necessary.
- c. All non-moving structural parts (i.e., bolts, laminations, and fixed castings) are assigned a minimum lambda of .001 failures/million hours.
- d. All moving components subject to failure and wear are assigned a minimum lambda of .07 failures/10<sup>6</sup> hours (except where contrary data are available).
- e. Calculations of bearing failure rates are adjusted for the low rotational speeds of the rotor shaft, VARCS shaft and yaw column.
- f. Component lambdas are corrected for estimated real cycles per hour.




Figure 10 HR2 Reliability Flow Chart

#### 11.0 MAINTENANCE PROCEDURES

The following is the routine maintenance procedure which should be conducted on the HR2 wind system at least once within any 365 day period to assure proper operation and long life of the SWECS. No preliminary maintenance is required at time of installation.

#### Annual Maintenance Procedures

- 1) Observe operating machine in wind in excess of 4 m/s (9 mph). Look and listen for any irregular operation, e.g.:
  - a. Erratic pitch or yaw motion
  - b. Rotor or system vibration
  - c. Tower vibration
  - d. Power output significantly reduced
  - e. Unusual noise
- 2) Crank machine into service position (90 degree pitch-back).
- 3) Inspect and tighten, as necessary, all mechanical fasteners. (See Installation Section of Maintenance Manual for bolt torques.)
- 4) Check blade surfaces for cracks, breakage, erosion.
- 5) Inspect all brushes and slip rings for wear. Replace brush sets if there is less than 1/2 inch remaining. Be careful not to lose the spring from the inside of the housing during inspection.
- 6) All bearings are lubricated with Shell "Aeroshell" 7 at the time of manufacture. Bearings should only be lubricated with Aeroshell 7 or compatible equivalent. Grease fitting locations are 1) at the top of the stub tower, 2) on the front face of the alternator at the shaft, 3) at the rear of the alternator shaft, accessible by removing the diode cover.
- 7) Return machine to operating mode slowly.

#### 12.0 CONCLUSIONS

Contractor testing of the prototypes has been completed. This program has been successful in meeting the goals of developing a product suitable for commercialization in the intended applications. Fabrication of the first prototype indicated a number of design changes which were immediately implemented in all three prototypes. Through the program of parallel testing by North Wind and Rocky Flats, running time was nearly doubled and the overall testing and redesign process accelerated.

Based on the HR2 test experience, North Wind has a high degree of confidence in the components and systems of the high reliability wind system. The present configuration of the commercial HR2 is representative of the critical design area modifications that were made as a result of both Rocky Flats and North Wind Power Company free-stream test programs.

#### 13.0 REFERENCES

- North Wind Power Company 2 Kilowatt High Reliability Wind System,
  Phase I Design and Analysis, July 1981, D. J. Mayer and J. H.
  Norton, Jr., North Wind Power Company, Inc., (RFP-3310/2).
- 2. North Wind Eagle 3 Wind Turbine Generator, Final Test Report, January 1980, J. H. Sexton, Rocky Flats Wind Systems Program, (RFP-3071).

# APPENDIX A Drawing Revisions

DRAWING DESCRIPTION: Master Drawing

REVISIONS: Delete front vent

Delete Pyle-National Connector

Add power cable boot Simplify power conduit Simplify VARCS spring hub

Redraw VARCS bearings as spherical roller type

Change VARCS centerline to rotor hub distance to reflect final

endbell dimensions

Change diode mounting lock detail

Delete O-ring seals

Change VARCS Disc dimension to reflect final design

R1-Add centerline offset at saddle

DRAWING NUMBER: 2K100

DRAWING DESCRIPTION: Alternator (Exploded View)

**REVISIONS:** 

R1-Bearing seal fasteners decreased to 1/4-20NC

R2-Delete O-ring seals

Add #406 woodruff key for sliprings

Delete front labyrinth seal retaining ring

DRAWING NUMBER: 2K111

DRAWING DESCRIPTION: Stator Laminations

**REVISIONS:** 

R1-Add material specification

DRAWING NUMBER: 2K12O

DRAWING DESCRIPTION: Lundels; Alternator Shaft

**REVISIONS:** 

R1-Rear bearing retainer ring seat added to shaft

R2-Shaft dimensions recalculated and corrected

R3-Corrected shaft taper angle as drawn

R4-Deleted front retaining ring seat at rear bearing

R5-Bore depth shortened on Lundel to allow .125" magnetic washer

DRAWING DESCRIPTION: Alternator Endbells

**REVISIONS:** 

R1-Keyseat deleted

R2-Front bearing seal mounting fastener holes reduced to 1/4-20NC

R3-Drawing changed to reflect ribbing detail

DRAWING NUMBER: 2K200

DRAWING DESCRIPTION: Rotor (Exploded View)

**REVISIONS:** 

R1-Transverse blade bolts 3/8-16NC R2-Hardware numeration updated

DRAWING NUMBER: 2K220

DRAWING DESCRIPTION: Rotor Hub Casting

**REVISIONS:** 

R1-Drawing changed to reflect new pattern work at nose cone rim

R2-Increase nose cone fasteners to 1/4-20NC

R3-Change nose cone fastener bolt circle diameter for production

nose cone

DRAWING NUMBER: 2K230

DRAWING DESCRIPTION: Nose Cone

**REVISIONS:** 

R1-Holes relocated for production rotor hub R2-Dimensions changed for production rotor hub

DRAWING NUMBER: 2K240

DRAWING DESCRIPTION: Rotor Hub Plate

**REVISIONS:** 

R1-Change flange direction 180° to correct drafting error

DRAWING DESCRIPTION: VARCS (Exploded View)

REVISIONS: Simplify power conduit
Simplify VARCS spring hub

Redraw VARCS bearings as spherical roller type

R1-Decrease power connector flange fasteners to 1/4-20NC

R2-Increase spring bracket bolts to 1/2-13NC

DRAWING NUMBER: 2K310

DRAWING DESCRIPTION: Alternator Support Casting

**REVISIONS:** 

R1-Delete VARCS bearing retainer ring seats

R2-Relocate grease fittings

R3-Add hole for Common connection

R4-Add cover holes

DRAWING NUMBER: 2K320

DRAWING DESCRIPTION: VARCS Shaft, Hub; Top Tower Plate

**REVISIONS:** 

R1-Add Top Tower Plate Revise VARCS hub

R2-Revise VARCS shaft for simplified VARCS hub

R3-Revise VARCS bearing seat dimensions

R4-Rotate VARCS bolt hole through VARCS shaft 30°

DRAWING NUMBER: 2K331

DRAWING DESCRIPTION: VARCS Spring

REVISIONS: Increase spring rate to 71 in-lb/degree

R1-Revise hole locations and effective spring length

DRAWING NUMBER: 2K333

DRAWING DESCRIPTION: VARCS Disc; Spring Bracket

REVISIONS: Revise VARCS disc interface with ASC

R1-Correct spring bracket material to ASTM 148-73

R2-Revise spring bracket dimensions for 3/4" cam followers

R3-Revise VARCS disc internal dimensions

DRAWING DESCRIPTION: VARCS Cover

REVISIONS: Add  $5^{\circ}$  draft to OD R1-Add 1" depth for new spring bracket and stop assembly

DRAWING NUMBER: 2K400, 500, 600

DRAWING DESCRIPTION: Stub Tower (Exploded View)

REVISIONS: Revise centerline offset and saddle ears

R1-Add slipring assembly key R2-Add brushholder part numbers

DRAWING NUMBER: 2K420

DRAWING DESCRIPTION: Saddle

**REVISIONS:** 

R1-Add longitudinal section R2-Rotate VARCS shaft seat

R3-Change centerline offset and casting configuration R4-Revise bearing seat dimensions and tail bolt holes

DRAWING NUMBER: 2K500

DRAWING DESCRIPTION: Tail Assembly

REVISIONS: Lengthen tail support arms

DRAWING NUMBER: 2K510

DRAWING DESCRIPTION: Tail Vane

REVISIONS: New Drawing

DRAWING NUMBER: 2K640

DRAWING DESCRIPTION: Tower Plate

**REVISIONS:** 

R1-Add slipring cover mounting holes R2-Tighten tower tube inset dimensions

R3-Revise cover hole dimensions

DRAWING DESCRIPTION: Power Brush Assembly Cover

REVISIONS: New Drawing

DRAWING NUMBER: 2K900

DRAWING DESCRIPTION: Field Regulator

REVISIONS: New Drawing